



Fact Sheet

Standiford Avenue (Dale Road to Sherwood Avenue) Pavement Rehabilitation Project

(last updated 4-30-2018)

Project Description:

Pavement rehabilitation project starting at Dale Road and proceeding east to approximately Sherwood Avenue. The length of the project is 2.97 miles. Anticipated project improvements include roadway resurfacing and/or reconstruction, new signage and striping, ADA upgrades, storm drainage system improvements, and signal upgrades (including detection cameras) where needed.

❖ Actual project limits are subject to change

Funding Source:

Measure L Funds – Local Street & Roads (Fiscal Year 2017-2018) - \$3,205,920

Project Budget:

Engineering/Design/Administration	\$225,000
Construction (Total)	\$2,980,920
TOTAL	\$3,205,920

Project Status:

Design is 95% complete. Anticipate posting project for bidding on May 9, 2018 with a Bid Opening on May 29, 2018. Anticipate awarding construction contract June 2018.

STANDIFORD AVENUE PAVEMENT REHABILITATION, DALE TO SHERWOOD					
Item	Description	Unit	Quantity	Unit Price	Total
1	Prepare and Maintain Stormwater Pollution Prevention Plan	LS	1	\$15,000.00	\$15,000.00
2	Lead Compliance Plan	LS	1	\$7,000.00	\$7,000.00
3	Traffic Control and Construction Area Signs	LS	1	\$225,000.00	\$225,000.00
4	Portable Changeable Message Sign	EA	6	\$5,000.00	\$30,000.00
5	Monument Preservation	LS	1	\$40,000.00	\$40,000.00
6	Remove and Replace Curb Ramp	EA	44	\$7,000.00	\$308,000.00
7	Removal and Installation of Striping, Markings and Signage	LS	1	\$250,000.00	\$250,000.00
8	Traffic Detection Cameras	LS	1	\$320,000.00	\$320,000.00
9	Cold Plane Asphalt (0.12')	SF	1,157,329	\$0.36	\$419,803.39
10	Hot Mix Asphalt (TYPE-A, 0.15' Thick)	TON	13,020	\$70.00	\$911,400.00
				Construction Contract	\$2,526,203.39
				Const. Admin. @ 10%	\$252,620.34
				Contingency @ 8%	\$202,096.27
				Design	\$225,000
				Total	\$3,205,920.00

Standiford Avenue Typical Cross-section
Existing / Proposed
75' to 80' Wide

